



**PEACE & DEVELOPMENT ACTION
(PDA)**

TENDER DOCUMENT

FOR

**REHABILITATION OF 5 HEALTH FACILITIES WATER RETICULATION
IN AFGOOYE**

TENDER REFERENCE: T/PDA/SHF/2023/013

JUNE 2023

TABLE OF CONTENTS

SECTION I: INTRODUCTION.....	3
SECTION II: DESCRIPTION OF THE PROJECT	3
SECTION III: TENDER INFORMATION.....	3
ANNEX I: BID SUMMARY FORM.....	5
ANNEX II: SUBMISSION FORM.....	6
ANNEX III: FORM OF DECLARATION.....	7
ANNEX IV: FOR OF INFORMATION OF THE BIDDER.....	8
ANNEX V: BILL OF QUANTITIES.....	9

1. Introduction

Peace and Development Action (PDA) is registered with the Government of the Federal Government of Somalia as Non-Governmental and Not-for-Profit Organization with a vision is to be a leading Somali-based Non-Governmental Organization that strengthening the capacity and expression of ordinary citizens to become resilient and participate freely in the sustainable development of Somalia. Key thematic areas of intervention include; Democracy & Good Governance, infrastructure development, food security, gender mainstreaming, peacebuilding & conflict resolution, food security, participatory budgeting and human rights advocacy.

2. Description of the project

In partnership with Somalia Humanitarian Fund (SHF), PDA intend to award a contract to a contractor rehabilitate five health facility water infrastructure in Voluntary Midwifery Service (VMS), Kuusow IDPs camp, Carbiska MCH, Afgoye orphanage health post and If iyo Aakhiro section in Afgooye district, through Construction of elevated water, tanks for storage, Piping and construction of water kiosks in Afgooye region as per the attached BoQ

3. Tender Information

Interested bidders must be registered, and holders of a valid construction permits issued by the Federal Government of Somalia. The bidders must also be in possession of qualified technical team which is able to perform the desired work perfectly and to the required technical standards. The bidders must be in possession of construction equipment able to rehabilitate five health facility water infrastructure in Voluntary Midwifery Service (VMS), Kuusow IDPs camp, Carbiska MCH, Afgoye orphanage health post and If iyo Aakhiro section in Afgooye district, through Construction of elevated water, tanks for storage, Piping and construction of water kiosks in Afgooye region

Interested bidders must possess the following Building equipment:

- Service trucks, etc.
- Welding equipment
- Water tank
- Hand tools

The company staff must meet the following qualification or expertise:

- A specialist in construction in engineering,
- Adequate number of support staff to ensure timely service delivery.

Participation:

This tender is open to interested eligible construction and engineering companies or individuals, legally registered in Federal government of Somalia, with permits to operate in Afgooye district, South West region state and with proven experience in the construction sector.

Language, System of Units and Currency of the Bids:

The bid prepared by the bidder and all documents related to the bid must be written in English only. The measurement units used in these bid documents are as in Annex V (Bill of Quantities). The bidders are required to use the same. The currency of this bid shall be in USD (\$). Quotations stated in other currencies will not be considered during the awarding process.

Contradiction or errors in the bid documents:

If the bidder notices contradictions or errors in the bid document or specifications that are unclear, the bidder must clarify the issue by enquiring before deadline for submission of bids

Duration of Contract:

The estimated duration of the contract proposed by PDA shall be a maximum of three (3) months from the time of signing the contract. If the contractor has a difference in duration, this should be indicated in the offer.

Selection Criteria:

Tenderers not providing all the requested documents and information necessary for evaluation as outlined in this tender document will automatically be disqualified from competing in this process. Additionally, the following will be used as an elimination criterion for participation in this process:

- Non-submission of price of all items in the BOQ
- Incomplete Bid Submission
- Late Bid Submission

Submission of the Bids:

The bid indicating the full name and contact details of the bidder and containing all requested information, must be presented to PDA Office in Mogadishu or Afgooye in a sealed envelope or can be sent by email to procurement@pda.org.so with complete tender reference number at the email subject.

Original copy of the bid documents with signature, date and stamp of the bidder must be put in a sealed envelope clearly marked “**Tender for the rehabilitation of 5 health facilities water reticulation in Afgooye**”

REF NO: T/PDA/SHF/2023/013

The sealed envelope containing Documents to be submitted above must be deposited at the PDA offices:

On or before 3.00 PM on 1st July 2023. Please make sure to sign at the logistics office when submitting the bid document. Late submission of offers will not be allowed.

ANNEX I

BID SUMMARY FORM

In response to:

TENDER INVITATION FOR REHABILITATION OF 5 HEALTH FACILITIES WATER RETICULATION IN AFGOOYE

I hereby provide PDA with the following offer:

Name of Contractor: _____

Financial offer: _____

Validity of offer: _____

Delivery date: _____

Payment terms: _____

Authorized by: _____

(Name, title, signature)

Date: _____

Annex II

Submission form

Interested parties should provide documents on the following selection criteria:

A) Company Information/ legal Status

A1: Company profile with full address (including contact person) and Contacts of the Bidder;

A2: Certificate of registration for both the Federal government and South West state region

A3: Valid construction works certificate Permit

A5: Valid Income Tax Clearance Certificate

B) Technical Capacity

The interested party is to list below details of all works of a similar nature carried out as Main Contractor over the last 2 years. The Values shall be in USD as appropriate.

Attach proof of successful completion.

Project – type of project completed	Name of client and address/ contact person	Location and year of completion	Value of contract (USD)
Construction 1.			
Construction 2.			
Construction 3.			
Construction 4.			

C) Financial Capacity

Attach most recent copy of:

- Certified bank statement (over the last 3 months)

Annex III

FORM OF DECLARATION

I hereby certify that all the information given above are true and I understand and acknowledge the fact that my Company is liable to be disqualified at any time during tendering process in case any of the information furnished by myself is not found to be true. Yours Faithfully,

Signature:

Position:

Name of Company: _____

Name of Chief Executive Officer: _____

Place: _____

Date: _____

Annex IV

FORM OF INFORMATION OF THE BIDDER

Name of the Company: _____

Name of Representative: _____

Address: _____

Valid mobile number(s): _____

Email address: _____

Name, title and contact information of the person(s) authorized to sign documents, receipts contracts, invoices, and report at the construction site or at the head office:

Contractor: _____
(In capital letters)

Signature: _____

Name: _____
(In capital letters)

Place: _____ Date: _____

Annex V:

Bill of Quantities (BoQ)

Rehabilitation of 5 health facilities water reticulation in Afgooye

#	Description	Unit	Unit quantity	Unit Cost	Total
A	Health Facilities water reticulation				
1	<u>General works</u>				
	<u>EXCAVATION AND SITE CLEARANCE</u>				
1.1	Provide labour and desilt well to increase depth by 2m. Rate to include for dewatering pump use for 48hours	Casuals* Manhours	48.0		
1.2	Excavate for sanitary seal and apron around the well 1000mm deep and dispose off excavated material n.e 100m	CM	19.7		
1.3	Excavate pit holes for protection fence 300mm girth over soft and rock formation n.e 600mm	CM	4.3		
1.4	Excavate for soak pit 1500m diax2500mm deep	CM	5.2		
1.5	Clear site all loose excavated materials with proper drainage off structures slope 1:1.5	Ls	1.0		
PAGE TOTAL CARRIED TO BILL COLLECTION SHEET C/F1					
A	Construction of well Apron, trough and soak pit				
1	Element 1: Masonry and sanitary seal works				
1.1	300mm thick approved hard-core, well compacted in layers not exceeding 150mm and blinded using 50mm murrum/quarry dust to foundation	SM	10.2		
1.2	150 x225X 450mm natural stone to apron and trough walling in 1:3 sand/cement mortar finished with steel finished on one	SM	26.0		

	side. Rate to included mild all reinforcement at every alternate course				
	Carried to Collection				
2	Element No.2: Concrete Work				
2.1	Vibrated concrete ration 1:2:3 around well 300mm girth to depth n.e 1000mm from surface as concrete seal. Provide for water proof ratio 1:1	CM	1.2		
2.2	Reinforced concrete grade 25/20 - 100mm thick floor slab to both apron and trough	CM	2.3		
2.3	Reinforced concrete grade 25/20 - 450 X 100mm footing for masonry wall	CM	2.2		
2.4	Fabricate for soak away pit and well access manhole covers 1000mmx1000mm. Use R8 rebars for reinforcement and provide for handles	No	2.0		
	Carried to Collection				
3	Element No. 3: Concrete Ancillaries				
3.1	Formwork				
	Provide cut and fix in position sawn timber formwork or equivalent.				
3.1.1	b) edges around slab 125mm wide	M	22.0		
3.2	Reinforcement				
	Steel reinforcement cut, bend & placed in position, unit price to include cutting, bending & placing in position with binding wire and concrete seats				
3.2.1	a) Mesh 142 mild steel reinforcement mesh (0.40kg/m2) on slab around apron and trough	SM	15.6		
	Carried to Collection				
4	Element No.5: Pipes and Fittings				
4.1	Fabricated 2" dia GI "B" drainage pipe to animal trough length 600mm threaded both ends	Pcs	1.0		
4.2	2" dia end cap to drainage pipe	Pcs	1.0		
	Carried to Collection				
5	Element No.6: Finishes				
5.1	Supply materials and provide for smooth trowel finish screed ratio 1:3 to wall surfaces for apron, trough and soakaway pit manhole. Rate to include for water proof to animal trough mix	SM	12.0		

5.2	Screed to apron and trough slab surfaces. Rate include for water proof	SM	6.2		
	Carried to Collection				
6	Supply materials hardcore pack and construct soak away pit for drainage from animal trough				
6.1	Hardcore parking to pit	CM	1.6		
	Carried to Collection				
	SUMMARY				
1	Element 1: Masonry and sanitary seal works				
2	Element No.2: Concrete Work				
3	Element No. 3: Concrete Ancillaries				
4	Element No.5: Pipes and Fittings				
5	Element No.6: Finishes				
6	Soak pit hardcore packing				
PAGE TOTAL CARRIED TO BILL COLLECTION SHEET C/F2					
B	<u>CONSTRUCTION OF FENCE AND GATE 3mx3m around well</u>				
1.1	Supply transport to site and install @2500mmc/c concrete poles 2400mm tall and 100mmx100mm CS/area with provision for barbed wire line holes (3mby3meter with one m height up grading wall by fixign steet sring chilink aproof by eng)	No	18.0		
1.2	Supply and install 1500mmx1800mm grill gate complete with all iron mongery and install. Use 25x25x6mm SHS with 75x75mmx6mm SHS poles firmly concreted to ground depth 750mm. Provide for primer and final gloss paint	LS	1.0		
	<u>Supply, transport to site and install; Rate to include for binding and jointing</u>				
1.3	G10 chainlink	SM	32.0		
1.4	Barbed wire 16g, 20kg -6 strand	LM	80.0		
1.5	CONCRETE WORKS				
	<u>Rate shall include handling, vibrating and curing</u>				
	Mass concrete class C20/25 in:				
1.5.1	To poles	CM	0.8		
1.5.2	300mmx300mm Gate support poles	CM	0.3		
	Finishes				
1.5.3	Stone pitching to chainlink base ratio 1:3:6	CM	0.7		
PAGE TOTAL CARRIED TO BILL COLLECTION SHEET C/F3					
C	Installation of Afridev hand pump				

	Supply and install Afridev Hand pump complete with pedestal, head assembly, pump cylinder, 12mm connecting rods, with PVC pipes class D. Well depth is 25 m deep.	Ls	1.0		
	Provide 67% chlorine powder and disinfect well as per guideline provided by engineer	Ls	1.0		
	PAGE TOTAL CARRIED TO BILL COLLECTION SHEET C/F4				
	COLLECTION SUMMARY				
	TOTAL COLLECTION C/F1				
	TOTAL COLLECTION C/F2				
	TOTAL COLLECTION C/F3				
	TOTAL COLLECTION C/F4				
	Total for one health facility water rehabilitation				
	Total for 5 health facilities water rehabilitation				